

John R. Clark Farm
HO-880
5159 Beaverbrook Road, Columbia
Howard County
Ca. 1870-1940s
Private

The John R. Clark Farm complex is located in the middle of a ca. 1950-1990s subdivision called Beaverbrook off of Route 108 (Clarksville Pike) in Columbia, Howard County. The building complex is set on a 5.2-acre lot at the top of a rise. The complex includes a ca. 1870 house that was remodeled in the 1930s, a ca. 1870 tenant house, a ca. 1870 wagon shed, a 1937 garage, a 1937 smoke house, and a 1940s workshop.

The farmhouse (ca. 1870, remodeled in 1937), in good condition, is main building on the property. The building is a 2 1/2 story side-gable house with a rear ell. The main house is 5-bays x 2-bays, the rear ell is 3-bays x 1-bay, and the house has an L-shaped footprint. Set on a stone foundation, the house was remodeled in ca. 1937 and now has stuccoed facades, a slate roof, and stone porches. Boxed wood cornices with projecting eaves and returns (now encased with siding) cap the facades. The main house has recent replacement windows, while the older ell retains some wood six-over-six windows. A ca. 1937 sunporch is located west of the main house and a ca. 1940s 1-story kitchen addition is located west of the rear ell. The main house has a center-passage, double-parlor plan and the rear ell has a side-passage plan.

The John R. Clark Farm is significant as a farm complex that is associated with events that have contributed to the broad pattern of the history of Howard County, Maryland. From founding Howard County families to current suburban surroundings, the building and landscape at the John R. Clark Farm represent Howard County's evolution from 19th century farmland to 20th c. suburb. The buildings on the property represent three owners of the farm: two farm families with extensive landholdings in the area and a Baltimore lumberman. The development of the property, from ca. 1870-1940s, represents evolution in farmhouse design, farmstead plans, and agricultural building typologies. Although the house was altered in the 1930s, the form of the ca. 1870 house remains clearly legible, and the ca. 1930s features have attained significance on their own, demonstrating the influence of national stylistic trends on country estates of the period.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. HO-880

1. Name of Property (indicate preferred name)

historic John R. Clark Farm

other "Beaverbrook"

2. Location

street and number 5159 Beaverbrook Road ___ not for publication

city, town Columbia ___ vicinity

county Howard

3. Owner of Property (give names and mailing addresses of all owners)

name Stanford and Jane Hooker

street and number 5159 Beaverbrook Road telephone 410-715-6589

city, town Columbia state MD zip code 21044

4. Location of Legal Description

courthouse, registry of deeds, etc. Howard County Land Record liber 1710 folio 400

city, town Columbia tax map 30 tax parcel 246 tax ID number 05-344468

5. Primary Location of Additional Data

- ___ Contributing Resource in National Register District
- ___ Contributing Resource in Local Historic District
- ___ Determined Eligible for the National Register/Maryland Register
- ___ Determined Ineligible for the National Register/Maryland Register
- ___ Recorded by HABS/HAER
- ___ Historic Structure Report or Research Report at MHT
- ___ Other: _____

6. Classification

Category	Ownership	Current Function	Resource Count	
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	Contributing	Noncontributing
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	6	0
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	0	0
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic	0	0
<input type="checkbox"/> object		<input type="checkbox"/> education	0	0
		<input type="checkbox"/> funerary	6	0
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory	
			0	

7. Description

Inventory No. HO-880

Condition

excellent deteriorated
 good ruins
 fair altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The John R. Clark Farm complex is located in the middle of a ca. 1950-1990s subdivision called Beaverbrook off of Route 108 (Clarksville Pike) in Columbia, Howard County. The building complex is set on a 5.2-acre lot at the top of a rise. The complex includes a ca. 1870 house that was remodeled in the 1930s, a ca. 1870 tenant house, a ca. 1870 wagon shed, a 1937 garage, a 1937 smoke house, and a 1940s workshop.

Farmhouse

The farmhouse (ca. 1870, remodeled in 1937), in good condition, is main building on the property. The farmhouse is a 2 1/2 story side-gable house composed of the ca. 1870 house with a rear ell. The ca. 1870 date of construction is based on deed and map research. In 1866, William Clark left the property where the John R. Clark Farm is located to his children John R. Clark and Rachel Clark. The 1878 Hopkins Atlas shows a house in the location of the John R. Clark Farm owned by John R. Clark. Some features of the attic framing of the rear ell, as well as the composition of its east facade, suggest that this section may have been constructed first and may be older than ca. 1870. Further examination of the building materials and construction technology should be conducted in a deeper investigation of the building.

The main house is 5-bays x 2-bays, the rear ell is 3-bays x 1-bay, and the house has an L-shaped footprint. Set on a stone foundation, the house was remodeled in ca. 1937 and now has stuccoed facades, a slate roof, and stone porches. Boxed wood cornices with projecting eaves and returns (now encased with siding) cap the facades. The main house has recent replacement windows, while the older ell retains some wood six-over-six windows. A ca. 1937 sunporch is located west of the main house and a ca. 1940s 1-story kitchen addition is located west of the rear ell. The main house has a center-passage, double-parlor plan and the rear ell has a side-passage plan.

main house

The primary facade of the main house faces north. The 5-bay primary facade is symmetrical about its entry bay. Openings are vertically aligned and graduated. The centered entry door configuration consists of the front door opening with a two-light over one-panel sidelights and a three-light transom. The entry door opening holds a ca. 1937 wood door, is framed by wood pilasters and cornice and covered by a ca. 1937 entry door hood with a triangular pediment supported by flared square columns. A flagstone walk leads to the front door, and three stone steps provide the transition to a broad stone veranda that extends across the front of the house, all added in ca. 1937.

The east (side) facade of the main house is two bays wide. A ca. 1937 stone and brick exterior fireplace chimney is centered on the gable end. Window openings on the 1st and 2nd stories are vertically aligned and graduated. Small attic story window openings flank the chimney. One cellar story window opening, which is vertically aligned with the 1st and 2nd story openings, is located north of the chimney. A metal cellar bulkhead entry is located south of the chimney.

The rear ell and ca. 1940s kitchen addition project from the south (rear) facade of the main house and largely conceal that facade. A western 1st story window opening and the western and centered 2nd-story window opening remain visible on the south facade of the main house.

The west (side) facade of the main house is two bays wide. A ca. 1937 1-story sunporch addition extends across the 1st story. The 2nd story has two symmetrically placed window openings. Two small attic story window openings flank the interior brick chimney. The 1-story, ca. 1937 sunporch, which has a stone foundation and stuccoed facades, projects from the house's west facade. Each of its visible facades (north, south, and west) has one centered pair of window openings that hold one-over-one replacement windows.

rear ell

The primary facade of the rear ell faces east. The 3-bay primary facade has its entry opening in the north bay. Openings are vertically aligned and graduated. Wood pilasters and cornice frame the entry door opening. A stone veranda, constructed in two sections, wraps the east and south side of the ell. A 1-story wood porch with flared square wood columns extends across the east facade.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. HO-880

Name
Continuation Sheet

Number 7 Page 1

The 1-bay gable end facade has one window opening at each the 1st and 2nd stories. A canvas awning covers the veranda south of the rear ell and kitchen addition. The ca. 1940s 1-story shed-roofed kitchen addition extends across the rear ell's west facade. The 2nd story of the rear ell has one window opening, located near the south end of the facade.

The 1-story kitchen addition was constructed in two sections, based on seams in the foundation and the stuccoing. The main section has one visible elevation, which faces west. The foundation of this section is constructed of stone-faced CMU. This elevation has two infilled window openings and one centered large window opening that holds a recent bay window. The south section of the kitchen addition houses a powder room and pantry. It has no openings in its west facade and one door opening and one window opening in its south facade, which opens onto the veranda.

interior

The interior of the ca. 1870 main house has a center-passage, double-parlor plan. The house retains its original floor plan and many features and finishes including a substantial Italianate stair and original plaster walls. Some features were reworked as part of the 1937 rehab. Wood strip flooring was installed over the original wood floors, some interior trim was replaced, new fireplace mantles were installed, and a pair of large door openings that lead to the sunroom were cut through. The 2nd floor has three bedrooms off of the center passage. The attic is partially finished for servant's quarters. Attic rafters in the main house are circular sawn, are mitered and butted at the ridge, and are secured with cut nails.

The interior of the rear ell has a side passage plan. The passage provides access between the main house, dining room, and kitchen. A closet and a cellar door are also located in the passage. The 1st floor room is used as the dining room. The 1st floor walls were stuccoed in ca. 1937 and wood strip flooring was installed. The 2nd floor is accessible via the main house and houses one bedroom. The attic is unfinished. Attic rafters in the rear ell are sash sawn, and are mitered and joined at a ridge pole.

Tenant house

The property retains a ca. 1870, 3-bay, tri-gable, tenant house located southeast of the main house. The tenant house, which has a stone foundation, is currently sheathed in replacement siding and has an asphalt roof and replacement windows. The house is set on the slope at the rear of the property and has a raised basement to the back. A one-story, 20th c. addition extends across the back of the house. The house has a single-pile, double-cell interior plan.

The primary facade of the tenant house faces north. The 1st story has a door opening flanked by window openings. The door opening, which holds an early 20th c. wood four-light over two-panel door, is located west of center because of the two-room interior plan. The 2nd story has two window openings that are vertically aligned with the 1st story window openings. The attic gable has one opening, now covered with siding, that is visible from the interior of the attic. A one-story, hipped-roof porch extends across the front facade. The porch has square wood posts and a concrete deck that is almost flush with the ground.

The east (side) facade of the house is composed of the main house and the 1-story rear addition. The main house is one bay wide. Centered, vertically aligned, window openings are located at the 1st and 2nd stories and a door opening is located at the cellar level. The 1-story addition is one bay wide. Centered, vertically aligned, window openings are located at the 1st and cellar stories.

The south (rear) facade of the house is composed of the rear facade of the main house and the south facade of the one-story addition. Because the one-story addition extends across the rear facade of the main house, only the 2nd story of the main house is visible. The 2nd story of the main house has one window opening, located in the western bay. The gable end of the 1-story rear addition has a compound roof form because the addition originally included an open porch (now enclosed) that faced west. The rear facade of the addition has two 1st-story window openings: one is located east of the gable and one is located in the enclosed section of the porch. The cellar story has two openings: one is a window opening that is vertically aligned with the 1st story window opening east of the

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. HO-880

Name
Continuation Sheet

Number 7 Page 2

gable and one is a door opening located west of the gable. The cellar window is a three-light wood window and the cellar door is a three-light over two panel wood door, both of which are original to the addition.

The west (side) facade of the tenant house is composed of the main house and the 1-story rear addition. There are no openings in the west facade of the main house. The west facade of the 1-story addition is the facade of the enclosed porch, which holds one door opening and one window opening.

Wagon Shed

A ca. 1870 wagon shed is located east of the main house. The wagon shed is a end-gable, timber-frame building set on stone piers with replacement wood siding and a corrugated metal roof. Some stone piers have been replaced with CMU.

The primary facade of the wagon shed faces north. The north facade is sheathed in board and batten siding. On the north facade, the centered entry door opening is flanked by a pair of vehicular openings. The entry opening, with pediment, holds a wood beadboard door. A loft door is centered in the gable.

The east and west facades are sheathed in vertical wood siding and do not have any openings.

The south facade is sheathed in vertical wood siding and has two door openings. The western opening is a vehicular opening with a sliding wood beadboard door. The eastern opening is an entry door opening with a wood door.

Smokehouse

The ca. 1937, 1-story, side-gable smokehouse is located south of the main house. The smoke house is constructed of rusticated CMU and has an asphalt roof. The primary facade of the smokehouse faces north. The door opening is centered in the north facade and holds a heavy wood door with diagonal board panels. The interior of the smokehouse is a single cell space. The wood framed roof displays the characteristic black discoloration from smoking meats. The east, west, and south facades do not have any openings.

Garage

The ca. 1937, 1-story, side-gable garage is located south of the main house. The garage is constructed of rusticated CMU and has an asphalt roof. The primary facade of the smokehouse faces north and is three bays wide. Three vehicular openings, which hold recent paneled garage doors, span the front facade. The east, west, and south facades do not have any openings.

Workshop/Bunkhouse¹

The ca. 1940s, 2-story, side-gable, workshop is located southwest of the main house. The building is constructed of CMU, has steel windows, wood beadboard doors, and an asphalt roof. The window openings have wood lintels. The building is set into the slope behind the house, so that the north facade is 1-story in height and the south facade is 2-stories in height.

¹ The current owner was told that the building was used as a barracks for German WWII Prisoners of War who worked on local farms. The building could also have been used as a bunkhouse for seasonal workers or as a workshop.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. HO-880

Name
Continuation Sheet

Number 7 Page 3

The primary facade of the building faces south and is 15 bays wide. The 1st and 2nd story openings are vertically aligned. From east to west the first story pattern of window and door openings is w, d, w, w, w, d, w, w, w, d, w, w, w, d, w. All fifteen 2nd-story openings are windows. The east (side) facade has one centered door opening that access the 2nd story. The west (side) facade is two bays wide. The 1st and 2nd story window openings are vertically aligned. The north (rear) facade, which faces the house, does not have any openings.

8. Significance

Inventory No. HO-880

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other: _____

Specific dates 1866, 1884, 1937, 1942, 1956, 1987 **Architect/Builder** unknown

Construction dates ca. 1870, ca. 1937, ca. 1940s

Evaluation for:
 National Register Maryland Register not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

The John R. Clark Farm is significant as a farm complex that is associated with events that have contributed to the broad pattern of the history of Howard County, Maryland. From founding Howard County families to current suburban surroundings, the building and landscape at the John R. Clark Farm represent Howard County's evolution from 19th century farmland to 20th c. suburb. The buildings on the property represent three owners of the farm: two farm families with extensive landholdings in the area and a Baltimore lumberman. The development of the property, from ca. 1870-1940s, represents evolution in farmhouse design, farmstead plans, and agricultural building types. Although the house was altered in the 1930s, the form of the ca. 1870 house remains clearly legible, and the ca. 1930s features have attained significance on their own, demonstrating the influence of national stylistic trends on country estates of the period.

Owners and occupants

The John R. Clark Farm has its roots in the vast 18th c. land holdings of the Worthington family. John Worthington left property in Howard and other counties to his son Nicholas Worthington. In 1845 Nicholas Worthington left a portion of his property to Nicholas Worthington Clark, son of William Clark. The 1860 Martenet's Map shows a house nearby the current location of the John R. Clark Farm, belonging to N.W. Clark. In 1861, Nicholas Worthington Clark conveyed the Worthington land to William Clark. In 1860, the William Clark family consisted of William Clark (aged 47) - farmer, his second wife Alvina (aged 37), and his nine children: John R. (aged 23) - lawyer & farmer, son Nicholas Worthington (aged 20) - farmer, daughter Rachel (aged 16), daughter Mary A. (aged 12), son William, aged 10, son Thaddeus (aged 8), son Thomas (aged 6), daughter Alvina (aged 2), and son Frank (aged 7 mos). A free African-American, Edward Anderson, (aged 35) was also a member of the household.² In 1866, William Clark conveyed 785 acres in the area to his son John R. Clark and daughter Rachel Clark. The 1878 Hopkins Atlas shows a house and farm at the current location of the John R. Clark Farm belonging to John R. Clark consisting of 235 acres.

In 1884, John R. Clark and Susan D. Clark sold the farm to William and Mary O'Donnell, who had emigrated to the U.S. from Ireland in the mid-19th century. In 1900, the O'Donnell family consisted of William (aged 76) - a farmer, Mary (aged 76), son William V. (aged 39) - who worked on the farm, daughter Mora (aged 37), daughter Katherine (aged 36), daughter-in-law Mary A. (aged 32), and farm workers Charles Earl (aged 19), and Shadrack Harding (aged 23).³ In 1906, William and Mary's children sold the farm their sibling William V. O'Donnell. In 1910, the O'Donnell family at the farm consisted of William (aged 49), wife Mary A. (aged 43), Son William (aged 9), daughter Mary (aged 7), daughter Blanche (aged 6), son John (aged 2), and daughter Dorothy (aged 8 months).⁴ William O'Donnell died in 1921 and left the farm to his widow and children.

The O'Donnells remained on the farm, but after the depression had to sell. In 1937, Mary Agnes O'Donnell sold the property to Milton and Emma Bosley, who were Baltimoreans. Mr. Bosley founded the Milton Bosley Co. architectural millwork supply business

² 1860, Fifth election district, page 8.
³ 1900, E. D. 87, Sheet 2A.
⁴ 1910, E. D. 57, Sheet 11A.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. HO-880

Name
Continuation Sheet

Number 8 Page 1

in 1913 and the firm is still in operation in Glen Burnie. The Bosleys rehabbed the house and presumably they also built the CMU garage and smoke house.⁵ The Bosley's ready access to lumber and millwork is visible in the character and quality of the rehabilitation.

In 1942, the Bosleys sold the farm to James and Bertha Brown. James Brown was the son of Dallas Brown, who farmed the property across the road (HO-186). James Brown eventually bought over 500 acres around the John R. Clark farm, where he raised cattle and grain. He had a butcher's shop in Ellicott City, where Paul's market is now (Paul worked for James).⁶

In 1956, James D. Brown, Jr. and Bertha M. Brown sold all but five acres surrounding the farmstead to a developer. Over the course of approx. 40 years the farm has transformed into a residential suburb, following the trend in much of Howard County. The Browns did not have any children and in 1987, Bertha Brown died and left the property to the Sekira family, who had taken care of her in her old age. The Sekiras owned the property until 2005 when Stanford and Jane Hooker bought the farmstead.

⁵ Jennifer Goold, telephone conversation with Senator James L. Clark, Jr. June 7, 2005.

⁶ Fred Dorsey write-up of Beaverbrook with information from Senator Clark.

9. Major Bibliographical References

Inventory No. HO-880

Department of Commerce – Bureau of the Census. **Census of United States: Population Schedule, 1860, 1870, 1900, 1910, 1920, 1930.**

Dorsey, Fred. Write up on Beaverbrook, from the author.

Goold, Jennifer. Phone conversation with Senator James Clark, Jr, June 7, 2005

Hopkins, G.M. **Atlas of Howard County, Maryland, 1878.** Ellicott City, MD: Howard County Bicentennial Commission, Inc., 1975.

Howard County Land Records, Dorsey Building, Columbia. See attached chain of title for specific libers and folios.

Martenet, Simon I. **Martenet's Map of Howard County, Maryland.** Baltimore, 1860

10. Geographical Data

Acreege of surveyed property 5.2 acres
Acreege of historical setting 235 acres
Quadrangle name Savage

Quadrangle scale: 1:24,000

Verbal boundary description and justification

The boundary of the John R. Clark Farm complex corresponds to Howard County Map 30, Grid 13, Parcel 246, which is the buildings' current legal lot.

11. Form Prepared by

name/title	Jennifer Goold, Historic Sites Surveyor		
organization	Howard County Department of Planning & Zoning	date	June 8, 2005
street & number	3430 Courthouse Drive	telephone	410-313-4335
city or town	Ellicott City	state	MD

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600

HO-880
 John R. Clark Farm
 5159 Beaverbrook Road, Columbia
 Howard County

CHAIN OF TITLE

GRANTOR	GRANTEE	DATE	LIBER	FOLIO	TRANS	PRICE	ACREAGE	COMMENTS
Charles E. Wehland, Personal Representative of the estate of Bertha M. Brown, deceased	Donald Hugo Sekira, Sr., Justine Elizabeth Sekira, Donald Hugo Sekira, Jr., David Sekira, Karen Sekira Affeldt, and Nancy Sekira	03-16-1987	1710	400	Deed	0.00	5.2	Being the portion of the land reserved in the Deed from James D. Brown, Jr., and wife to Town & Ranch Homes, Inc. dated October 22, 1956 (Liber 289, Folio 404). To be their sole and absolute property provided that said property shall not be sold, mortgaged or pledged as security for any loan or mortgage for TEN (10) years accounting from July 4, 1986, except under threat of condemnation, during said ten year period, then title to said property or the proceeds of sale thereof shall pass to the ANIMAL WELFARE SOCIETY OF HOWARD COUNTY, INC., a Maryland Corporation. The Grantees, as a condition of this conveyance, hereby agree to care for any animal owned by Bertha M. Brown at the time of her death. Said animal is to be housed and cared for in her home for the balance of its natural life.
James D. Brown, Jr. and Bertha M. Brown (Howard County)	Town & Ranch Homes, Inc.	11-22-1956	289	404	Deed	5.00	509.1 acres save 5.2 acres	All those two tracts which were conveyed to the grantors by 1) deed dated July 6, 1942 and recorded in Liber 175, folio 166 and by 2) deed dated October 23, 1944 and recorded in Liber 183, folio 464 and part of the parcel conveyed by 3) deed dated November 8, 1943 and recorded in Liber 179, folio 452. Said 5.2 acre parcel shall be used for residential purposes only and that the Grantors, their heirs and assigns, shall not be permitted to maintain on said parcel any animals other than domestic pets; and that the Grantors covenant for themselves, their heirs, personal representatives, executors and assigns, that said 5.2 acre parcel of land shall be continued as an entity and shall not be divided in any manner whatsoever.

HO-880
 John R. Clark Farm
 5159 Beaverbrook Road, Columbia
 Howard County


CHAIN OF TITLE

James D. Brown, Jr. and Bertha M. Brown	Milton W. Bosley	07-06-1942	175	168	Mortgage	25,000	1) 253.5 acres	
Milton W. Bosley	James D. Brown, Jr. and Bertha M. Brown	07-06-1942	175	166	Deed	5.00	1) 253.5 acres	Being the same piece or parcel of ground which by deed dated the 12th of January, 1937, and recorded in Liber 156, folio 76 was granted by Mary A. O'Donnell, widow and others, to Milton W. Bosley and Emma Bosley. Emma Bosley has since died.
Mary Agnes O'Donnell, et al	Milton W. Bosley and Emma Bosley	01-12-1937	156	76	Deed	5.00	1) 253.5 acres	Being the same property described in a Deed from Elizabeth Cooney, et al, to William O'Donnell, dated February 14, 1906 and recorded in Liber 81, folio 569. William O'Donnell died intestate on April 25, 1921, leaving surviving him are his widow and children and only heirs at law.
Catherine C. O'Donnell, et al	William O'Donnell	02-14-1906	81	569	Deed	15,000	1) 253.5 acres	et al = Elizabeth Cooney, Michael H. Cooney, her husband, Honora M. O'Donnell, Catherine C. O'Donnell, and Mary A. Brunsmann.
John R. Clark and Susan D. Clark (Howard County)	William O'Donnell (Howard County)	09-05-1884	48	267	Deed	10,711.36	1) 271 acres	Being a portion of the same property which John R. Clark obtained from William Clark by deed dated 19th October, 1866 (Liber 26, folio 67)

HO-880
 John R. Clark Farm
 5159 Beaverbrook Road, Columbia
 Howard County

CHAIN OF TITLE

William Clark and wife	John R. Clark and Rachel Clark	10- 19- 1866	26	67	Deed	10.00	(1) Appr ox. 785 acres	<p>Nicholas Worthington, son of John Worthington, deceased, died seized and possessed of land in Howard and adjoining counties. Nicholas Worthington in his will dated August 1, 1845 left Nicholas Worthington Clark, son of William Clark, certain portions of that land. Nicholas Worthington Clark, by deed dated June 1, 1861 and recorded in Liber 21, folio 532 conveyed all of that land to William Clark.</p> <p>William Clark wishes to convey portions of that land to his son, John R. Clark, and his daughter, Rachel Clark. Parcels composed of part of tract called "Felicity" totaling 541.25 acres, two parts of a tract of land called "Browns Forrest" containing 61.5 acres and 37.5 acres, and an additional unnamed section containing 20.5 acres for a total of 660.5 acres.</p> <p>Being the same property conveyed by the President, Directors, and Compnay of the City Bank of Baltimore to Nicholas Worthington of John on September 2, 1823 in A. A. Liber 9, folio 600.</p> <p>As well as part of a tract of land on the south side of the Montgomery Road called "Hammond's Inheritance" containing 99 acres, three roods, and thirty-eight perches, described in a deed from Richard Cromwell, Jr. and Elizabeth Ann Cromwell to Nicholas Worthington on Nov. 16, 1832 in A.A. Liber 23, folio 343, and</p> <p>All that parcel part of "Chews Vineyard contining 25.5 acres described in deed from Thomas B. Dorsey of John to Nicholas Worthington dated April 4, 1826 and recorded in A.A. Liber 11, folio 605.</p>
---------------------------	---	--------------------	----	----	------	-------	------------------------------------	--



HO-880

JOHN R. CLARK FARM CA. 1870, REMODELED 1937

MAIN HOUSE


JENNIFER GOULD

APRIL 2005


SCALE 3/16" = 1'0"



H0-880




SECOND FLOOR PLAN



H0-880
JOHN K. CLARK FARM
TENANT 3/16" = 1'0"



HO-880




HO-880

JOHN R. CLARK FARM

WAGON SHED 3/16" = 1'0"






HO-830
JOHN R. CLARK FARM

GARAGE

3/16" = 1'0" 




JOHN R. CLARK FARM

SMOKEHOUSE

3/16" = 1'0"

HO-880



HO-880

JOHN R. CLARK FARM

WORKSHOP

3/16" = 1'0"






John R. Clark Farm (HO-880)
5159 Beaverbrook Road, Columbia, MD
Howard County
Site Plan/Aerial Photo



John R. Clark Farm (HO-880)
5159 Beaverbrook Road, Columbia, MD
Howard County
Site Plan/Aerial Photo




John R. Clark Farm (HO-880)
 5159 Beaverbrook Road, Columbia, MD
 Howard County
 1878 Hopkins Atlas




John R. Clark Farm (HO-880)
5159 Beaverbrook Road, Columbia, MD
Howard County
USGS Savage Quad

James "Jimmie" Brown

c. 1942




Main House



Barns

H0-380
JOHN R. CLARK FARM



Aerial view of farmland



HO-880

JOHN R. CLARK FARM



Mowing Hay



View from bass lake

Grazing cattle

H10-880

JOHN R. CLARK FARM





HO-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPO

ART-2611 <NO.26A>027
522 1717 -1 N N-3-50 (044)0

Shows buildings in setting. Views.

lob 17



HO-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPO

Views w. shows bridge in setting.

20617

ART-2611 <NO.25A>B26
522 1212 -1 N N-5-41 <B44>B



HO-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2007

MD 8HPG

Views, Shows main house and tenant
house

306 H

ART-2611 <No. 27A>028
572 1217 - 1 N N-3-62 <044>0



HD-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD 8HPO

Views . Shows main house primary facade.

40617

ART-2611 <NO.28A>029
522 1717 - I N N-6-40 (044)@

Kodak Professional
PAPER

PAPER

PAPER



HO-880

Justice P. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPO

ART-2611 <No. 299>B3B
522 1217 -1 N N-5-31 <044>@

View SE. Shows front + side facades of
main house.

50617



HO-380

John A. - Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPO

ART-2611 <NO. 6A>004
529 1212 -1 N N-4-16 <044>0

View NE. Shows side + rear facades of ca.
1800's, 1840's sections of house.

606 17



HO-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPO

ART-2611 <NO. 7A>005
579 1212 -1 N-N-2-27 <B44>0

View W. Shows side facades of ca. 1800's +
ca 1840s sections of house.

7.6.17



H10-300

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPO

View S. Shows tenant house, front facade.

8 of 17

ART-2611 <NO. 349>035
572 1217 -1 N N-5-08 (044)0



HD-880

JOHN R. Clark Farm
Howard County, MD
Jennifer Goold

April 2005

MD SHPO

View N. Shows tenant house, rear facade.

906 17

ART-2611 <NO. 59>003
579 1212 - 1 N N T - 2 09 <044>0



HO-880

John R. Clark Farm
Howard County, MD
Jennifer Gould

April 2005

MD SHPO

view SE. Shows wagon shed, front + side
facades.

10 06 17

ART-2611 <NO. 35A>036
522 1217 - I N N-4-30 (044)0



HO-880

John R. Clark Farm

Howard County, MD

Jennifer Good

April 2005

MD-8HPO

View NW. Shows wagon shed, rear + side
facades

11 06 17

ART-2611 <NO. 8A>006
579.1212 -1 N N-4 30 (044)0



HO-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD 84PU

View SE shows garage, front + side
facades.

1206 17

ART-2611 <NO. 33A>B34
522 1212 -1 N N-3-21 <B44>©



HO - 880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MP SHPO

View SE. Snows Smoke house.

130617

ART-2611 <NO. 329>B33
522 1212 -1 N N-3 BT <B44>®



HO-880

John R. Clark Farm

Howard County, MD

Jennifer Gould

April 2005

MD SHPB

View NE Shows smokehouse and garage,
side and rear facades.

140617

ART-2611 (NO. 4A)002
579 1212 -1 N N 3 03 (844)0



HO-880

John R. Clark Farm

Howard County

Jennifer Gould

April 2005

MD SHPO

View N. Shows primary + side facades
of workshop.

1506 17

ART-2611 <NO. 3A>001
579 1217 -1 N-3-22 <044>0



HO-880

John R. Clark Farm

Howard County

Jennifer Goold

April 2007


MD SHPO

VIEW SE. Shows rear + side facades of

Workshop.

1606 17

ART-2611 <NO. 389>031
572 1717 - 1 N N-2-33 <044>0



HO-880

John A. Clark Farm

Howard County

Jennifer Gould

April 2005

MD SHPO

View N. Shows well.

170617

ART-2611 <NO.24A>025
572 1217 -1 N N-5 28 <044>0